BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT40943

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/28/2019-20, Date: 17.03.2020

Name of Work:Improvements to Solid waste management in ward no 5 Jakkur

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SANTHOSH B (VENKATESHWARASWAMY ENTERPRISES		
				In Figures		In Words
1	27.45	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80	Cum	217.88	5980.81	Rupees Two Hundred Seventeen and Eighty Eight Paise Only
2	6.86	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	5778.17	39638.25	Rupees Five Thousand Seven Hundred Seventy Eight and Seventeen Paise Only
3	15.34	KSRB 5.2-3: Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Pg No.25 Item No.5.6	Cum	5112.91	78432.04	Rupees Five Thousand One Hundred Twelve and Ninety One Paise Only
4	82.35	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, HOM curing complete as per specifications. Pg No.256 Item No.34.12.2	Sqm	155.75	12826.01	Rupees One Hundred Fifty Five and Seventy Five Paise Only
5	7.31	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)	Cum	6031.81	44092.53	Rupees Six Thousand Thirty One and Eighty One Paise Only
6	75	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) including cost of materials, labour, HOM complete as per specifications (P.No-266,I No-37.2)	M	955.61	71670.75	Rupees Nine Hundred Fifty Five and Sixty One Paise Only
7	164.7	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications. (P.No-266,I No-37.3)	Sqm	795.42	131005.67	Rupees Seven Hundred Ninety Five and Forty Two Paise Only

Signature of the contractor

16/03

Executive Engineer

	Approved Qty.	Description	Unit	Approved Tender Rates of SANTHOSH B (VENKATESHWARASWAMY ENTERPRISES		
				In Figures		In Words
8	183	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications. (P.No-266,I No-37.4)	M	453.89	83061.87	Rupees Four Hundred Fifty Three and Eighty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/05

16/05